

DEMOLITION PLAN LEGEND

	BUILDING TO BE REMOVED
	CONCRETE PAVEMENT TO BE REMOVED
	GRAVEL DRIVEWAY TO BE REMOVED
	FENCE TO BE REMOVED
	LIMIT OF DISTURBANCE
	SITE FEATURE TO BE REMOVED
	LIMITS OF TREE REMOVAL

CONSTRAINTS LEGEND

	WETLAND TRANSITION BUFFER
	FRESHWATER WETLANDS
	100-YEAR FLOODPLAIN
	NJ FLOOD HAZARD BOUNDARY
	DRCC STREAM CORRIDOR
	GREENBELT BOUNDARY
	STATE OPEN WATER
	RIPARIAN ZONE

- NOTES:**
- CONTRACTOR TO CONTACT 'NJ ONE CALL' PRIOR TO THE START OF CONSTRUCTION.
 - CONTRACTOR TO VERIFY THE LOCATION/ELEVATION OF ALL EXISTING UTILITIES WITHIN THE PROJECT LIMIT. SHOULD A CONFLICT BE DETERMINED THE ENGINEER OF RECORD SHALL BE CONTACTED.
 - EXISTING UTILITIES SHALL REMAIN AND BE PROTECTED THROUGH CONSTRUCTION.
 - REFER TO SHEET CS-503 FOR APPLICABLE DEMOLITION NOTES.
 - EXISTING TREES TO REMAIN AND BE PROTECTED THROUGH CONSTRUCTION UNLESS OTHERWISE NOTED ON THIS PLAN TO BE REMOVED. NURSERY TREES TO BE TRANSPLANTED PRIOR TO THE START OF DEMOLITION. COORDINATION TREE TRANSPLANTING WITH PRINCETON UNIVERSITY.
 - THE PROJECT SITE IS SUBJECT TO THE LETTER OF INTERPRETATION LINE VERIFICATION (LOI-V), DATED JANUARY 24, 2018 UNDER FILE AND ACTIVITY NO. 1113-02-0003.2 FWW170001.
 - 2,900 SF± OF EXISTING STRUCTURES/IMPERVIOUS SURFACES ARE PROPOSED TO BE REMOVED WITHIN THE BOUNDARY OF THE FRESH WATER WETLANDS TRANSITION BUFFER AND RESTORED WITH LAWN.

Date	Description	No.
11/11/2022	NJDEP FHA SUBMISSION #4	5.
9/16/2022	NJDEP FHA SUBMISSION #3	4.
8/10/2022	NJDEP FHA SUBMISSION #2	3.
6/30/2022	DESIGN DEVELOPMENT FINAL	2.
6/9/2022	NJDEP FHA SUBMISSION	1.

REVISIONS

Date	Description	No.
8/10/2022	CHRISTIAN ROCHE PROFESSIONAL ENGINEER NJ Lic. No. 24GE04988100	

LANGAN
Langan Engineering and Environmental Services, Inc.
989 Lenox Drive, Suite 124
Lawrenceville, NJ 08648
T: 609.282.8000 F: 609.282.8001 www.langan.com
NJ CERTIFICATE OF AUTHORIZATION No. 24GA27896400


Project: **CAMPUS OPERATIONS BUILDING - PRINCETON UNIVERSITY LAKE CAMPUS**
PRINCETON UNIVERSITY
WEST WINDSOR TOWNSHIP (BLOCK 3, LOT 1.012)
MERCER COUNTY NEW JERSEY

DEMOLITION PLAN



Project No. 130183501	Drawing No. DM-101
Date 06/09/2022	Sheet 1 of 14
Drawn By CJS	
Checked By CMR	

SCALE: 1 INCH = 30 FEET

PROJECT NO. 130183501



MAP REFERENCE: NEARMAP IMAGE DATED 29 JUNE 2022
SITE LOCATION
 SCALE: 1" = 1000'



SITE PLAN LEGEND

- BUILDING
- CONCRETE PAVEMENT
- GRAVEL DRIVEWAY
- REINFORCED TURF
- LAWN (SEED MIX 1)
- LAWN (SEED MIX 2)
- DOOR
- STORMWATER MANAGEMENT BASIN
- PROPERTY LINE
- LIMIT OF DISTURBANCE
- ACCESS GATE

CONSTRAINTS LEGEND

- WETLAND TRANSITION BUFFER
- FRESHWATER WETLANDS
- 100-YEAR FLOODPLAIN
- NJ FLOOD HAZARD BOUNDARY
- DRCC STREAM CORRIDOR
- GREENBELT BOUNDARY
- STATE OPEN WATER
- RIPARIAN ZONE

NOTES:

- THE PROJECT SITE IS SUBJECT TO THE LETTER OF INTERPRETATION LINE VERIFICATION (LOI-V), DATED JANUARY 24, 2018 UNDER FILE AND ACTIVITY NO. 1113-02-0003.2 FWW170001.
- STANDARD PARKING SPACE STRIPING SHOWN FOR DELINEATION ONLY, NO STRIPING TO BE PAINTED EXCEPT FOR HANDICAP SPACE / LOADING AREA MARKINGS AND PEDESTRIAN CROSSWALK STRIPES.

SCALE: 1 INCH = 30 FEET

Date	Description	No.
11/11/2022	NJDEP FHA SUBMISSION #4	5.
9/16/2022	NJDEP FHA SUBMISSION #3	4.
8/10/2022	NJDEP FHA SUBMISSION #2	3.
6/30/2022	DESIGN DEVELOPMENT FINAL	2.
6/9/2022	NJDEP FHA SUBMISSION	1.

REVISIONS

SIGNATURE: CHRISTIAN ROCHE 8/10/2022
 PROFESSIONAL ENGINEER NJ Lic. No. 24GE04988100

LANGAN
 Langan Engineering and Environmental Services, Inc.
 989 Lenox Drive, Suite 124
 Lawrenceville, NJ 08648

T: 609.282.8000 F: 609.282.8001 www.langan.com
 NJ CERTIFICATE OF AUTHORIZATION No. 24GA27896400

Project: **CAMPUS OPERATIONS BUILDING - PRINCETON UNIVERSITY LAKE CAMPUS**
 PRINCETON UNIVERSITY
 WEST WINDSOR TOWNSHIP (BLOCK 3, LOT 1.012)
 MERCER COUNTY NEW JERSEY



Drawing Title: **SITE PLAN**

Project No.	130183501	Drawing No.	CS-101
Date	06/09/2022		
Drawn By	CJS		
Checked By	CMR		

Sheet 2 of 14


RIP-RAP APRON (SEE L FOR DIMENSIONS AND STONE SIZE)

RIP-RAP APRON (SEE



NOTES:

- 100-YEAR FLOODPLAIN ELEVATION DETERMINED FROM NJDEP STATE STUDY AND FEMA 100-YEAR FLOODPLAIN. 100-YEAR FLOODPLAIN ELEVATION ON PROJECT SITE IS 57.0 (NAVD 88).
- NEW JERSEY FLOOD HAZARD AREA DESIGN FLOOD (NJFHADF) BOUNDARY DETERMINED FROM N.J. FLOOD HAZARD CONTROL ACT METHOD 1. NJFHADF BOUNDARY ELEVATION ON PROJECT SITE IS 58.5' (NAVD 88).



Date	Description	No.
11/11/2022	NJDEP FHA SUBMISSION #4	5.
9/16/2022	NJDEP FHA SUBMISSION #3	4.
8/10/2022	NJDEP FHA SUBMISSION #2	3.
6/30/2022	DESIGN DEVELOPMENT FINAL	2.
6/9/2022	NJDEP FHA SUBMISSION	1.

REVISIONS

Signature	Date
CHRISTIAN ROCHE	8/10/2022

PROFESSIONAL ENGINEER NJ Lic. No. 24GE04988100

LANGAN
 Langan Engineering and Environmental Services, Inc.
 989 Lenox Drive, Suite 124
 Lawrenceville, NJ 08648


T: 609.282.8000 F: 609.282.8001 www.langan.com
 NJ CERTIFICATE OF AUTHORIZATION No. 24GA27896400

Project: **CAMPUS OPERATIONS BUILDING - PRINCETON UNIVERSITY LAKE CAMPUS**
 PRINCETON UNIVERSITY
 WEST WINDSOR TOWNSHIP (BLOCK 3, LOT 1.012)
 MERCER COUNTY NEW JERSEY


Drawing Title

GRADING AND DRAINAGE PLAN


Project No. 130183501	Drawing No. CG-101
Date 06/09/2022	Sheet 3 of 14
Drawn By CJS	
Checked By CMR	



DRAINAGE PROFILE
(CB-3 - FES-2)



DRAINAGE PROFILE
(CB-6 - FES-1)



DRAINAGE PROFILE
(OCS-1 - MH-137)

Date	Description	No.
11/11/2022	NJDEP FHA SUBMISSION #4	5.
9/16/2022	NJDEP FHA SUBMISSION #3	4.
8/10/2022	NJDEP FHA SUBMISSION #2	3.
6/30/2022	DESIGN DEVELOPMENT FINAL	2.
6/9/2022	NJDEP FHA SUBMISSION	1.

REVISIONS

SIGNATURE CHRISTIAN ROCHE 8/8/2022
PROFESSIONAL ENGINEER NJ Lic. No. 24GE04988100

LANGAN

Langan Engineering and Environmental Services, Inc.
989 Lenox Drive, Suite 124
Lawrenceville, NJ 08648

T: 609.282.8000 F: 609.282.8001 www.langan.com
NJ CERTIFICATE OF AUTHORIZATION No. 24GA27896400


Project
CAMPUS OPERATIONS BUILDING - PRINCETON UNIVERSITY LAKE CAMPUS
PRINCETON UNIVERSITY
WEST WINDSOR TOWNSHIP (BLOCK 3, LOT 1.012)


MERCER COUNTY NEW JERSEY

Drawing Title


STORM PROFILES

Project No. 130183501	Drawing No. CG-201
Date 06/09/2022	Sheet 4 of 14
Drawn By DJD	
Checked By CMR	





UTILITY PLAN LEGEND	
—E—E—E—	ELECTRIC LINE
—W—	WATER LINE
—S—	SANITARY LINE
□	ELECTRIC HANDHOLE
⊙	SANITARY MANHOLE
⊕	VALVE



Date	Description	No.
11/11/2022	NJDEP FHA SUBMISSION #4	5.
9/16/2022	NJDEP FHA SUBMISSION #3	4.
8/10/2022	NJDEP FHA SUBMISSION #2	3.
6/30/2022	DESIGN DEVELOPMENT FINAL	2.
6/9/2022	NJDEP FHA SUBMISSION	1.

REVISIONS


SIGNATURE CHRISTIAN ROCHE 8/8/2022
 PROFESSIONAL ENGINEER NJ Lic. No. 24GE04988100

LANGAN
 Langan Engineering and Environmental Services, Inc.
 989 Lenox Drive, Suite 124
 Lawrenceville, NJ 08648
 T: 609.282.8000 F: 609.282.8001 www.langan.com
 NJ CERTIFICATE OF AUTHORIZATION No. 24GA27896400

Project **CAMPUS OPERATIONS BUILDING - PRINCETON UNIVERSITY LAKE CAMPUS**
 PRINCETON UNIVERSITY
 WEST WINDSOR TOWNSHIP (BLOCK 3, LOT 1.012)
 MERCER COUNTY NEW JERSEY
 Drawing Title

UTILITY PLAN

Project No. 130183501	Drawing No. CU-101
Date 06/09/2022	CU-101
Drawn By CJS	
Checked By CMR	
Sheet 5 of 14	



**SANITARY SEWER PROFILE
(EX. SAN BC-1 TO EX. SAN MH-101)**

Date	Description	No.
11/11/2022	NJDEP FHA SUBMISSION #4	5.
9/16/2022	NJDEP FHA SUBMISSION #3	4.
8/10/2022	NJDEP FHA SUBMISSION #2	3.
6/30/2022	DESIGN DEVELOPMENT FINAL	2.
6/9/2022	NJDEP FHA SUBMISSION	1.

REVISIONS

SIGNATURE: CHRISTIAN ROCHE 8/8/2022
 PROFESSIONAL ENGINEER NJ Lic. No. 24GE04988100


LANGAN
 Langan Engineering and Environmental Services, Inc.
 989 Lenox Drive, Suite 124
 Lawrenceville, NJ 08648
 T: 609.282.8000 F: 609.282.8001 www.langan.com
 NJ CERTIFICATE OF AUTHORIZATION No. 24GA27896400

Project
**CAMPUS OPERATIONS
 BUILDING - PRINCETON
 UNIVERSITY LAKE CAMPUS**
 PRINCETON UNIVERSITY
 WEST WINDSOR TOWNSHIP (BLOCK 3, LOT 1.012)

MERCER COUNTY NEW JERSEY
 Drawing Title

SANITARY PROFILES

Project No. 130183501	Drawing No. CU-201
Date 06/09/2022	Sheet 6 of 14
Drawn By DJD	
Checked By CMR	



MERCER COUNTY SOO REQUIRED SOIL EROSION AND SEDIMENT CONTROL NOTES

1. THE MERCER COUNTY SOIL CONSERVATION DISTRICT SHALL BE NOTIFIED 48 HOURS PRIOR TO STARTING LAND DISTURBANCE ACTIVITY. NOTICE MAY BE MAILED, FAXED OR EMAILED TO: MDCSD, 590 HUGHES DRIVE, HAMILTON SQUARE, NJ 08690...

PERMANENT STABILIZATION WITH SOOD

PERMANENT SODDING SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY. THE FOLLOWING SOO SCHEDULE SHOULD BE USED FOR PERMANENT STABILIZATION:

Table with 3 columns: Soil Texture, Limestone Application Rate by Soil Texture (Tons/Acre), and LBS./1000 SQ. FT.

TEMPORARY VEGETATIVE COVER FOR SOIL STABILIZATION

1. SITE PREPARATION
A. GRADE AS NEEDED AND FEASIBLE TO PERMIT THE USE OF CONVENTIONAL EQUIPMENT FOR LIMING, FERTILIZING, INCORPORATION OF ORGANIC MATTER, AND OTHER SOIL PREPARATION PROCEDURES...

STANDARD FOR TOPSOILING

TOPSOIL SHALL BE USED WHERE SOILS ARE TO BE DISTURBED AND WILL BE REVEGETATED. THE FOLLOWING SCHEDULE SHALL BE USED FOR MAINTENANCE OF VEGETATION:

MAINTENANCE OF VEGETATION

MAINTENANCE SHALL OCCUR ON A REGULAR BASIS, CONSISTENT WITH FAVORABLE PLANT GROWTH, SOIL, AND CLIMATIC CONDITIONS. THIS INVOLVES REGULAR SEASONAL WORK FOR MOWING, FERTILIZING, LIMING, WATERING, PRUNING, FIRE CONTROL, WEED AND PEST CONTROL, RESEEDING, AND TIMELY REPAIRS...

MAINTENANCE OF VEGETATION

MERCER COUNTY SOIL CONSERVATION DISTRICT 590 HUGHES DRIVE HAMILTON SQUARE, N.J. 08690 PHONE: (609) 586-9603 FAX: (609) 586-1117 MERCERSOIL@AOL.COM

CONTRACTOR MUST NOTIFY DISTRICT 48-HOURS PRIOR TO START OF CONSTRUCTION.

SOIL EROSION CONTACT

PERMANENT VEGETATIVE COVER FOR SOIL STABILIZATION (SHOWN FOR REFERENCE ONLY - ALL LAWN AREAS SHALL BE STABILIZED WITH SOO)
PERMANENT SEEDING SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE "STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY..."

Table with 3 columns: Date, Description, No.

SIGNATURE CHRISTIAN ROCHE 8/8/2022 PROFESSIONAL ENGINEER NJ Lic. No. 24GE04988100



CAMPUS OPERATIONS BUILDING - PRINCETON UNIVERSITY LAKE CAMPUS WEST WINDSOR TOWNSHIP (BLOCK 3, LOT 1.012)

MERCER COUNTY NEW JERSEY Drawing Title SOIL EROSION AND SEDIMENT CONTROL NOTES Project No. 130183501 Drawing No. CE-501 Date 06/09/2022


SOIL EROSION AND SEDIMENT CONTROL PLAN NOTES

MANAGEMENT OF HIGH ACID PRODUCING SOIL


STANDARD FOR DUST CONTROL

SEQUENCE OF CONSTRUCTION OPERATIONS


PERMANENT SEED MIX



SCOUR HOLE DETAIL



CONSTRUCTION GATE




6-FT TEMPORARY CONSTRUCTION FENCE


Table 29-1: Length of Construction Date on Slopes/Roadside

Percent Slope of Roadway	Length of Stone Required
2 to 5%	100 ft
5 to 10%	150 ft
10 to 15%	200 ft

> 5% Entire surface stabilized with Hot Mix Asphalt Base Course, Mix 1-2




STABILIZED CONSTRUCTION ACCESS




- NOTES:**
- SEDIMENT FILTER BAGS ARE FOR USE WITH ALL INLETS THAT ARE IN PAVED AREAS BUT ARE NOT ADJACENT TO CURBING.
 - SEDIMENT FILTER BAGS SHALL BE MANUFACTURED BY SILTSACK (REGULAR FLOW MODEL) OR APPROVED EQUAL.
 - LENGTH AND WIDTH OF FILTER BAG VARIES ACCORDING TO INLET SIZE.
 - OVERFLOW HOLES ARE REQUIRED A MINIMUM OF 1 FOOT ABOVE THE BOTTOM OF THE BAG.

SEDIMENT FILTER BAG INSERT



PROBING WIRE TEST 15.5 GA. STEEL WIRE (SURVEY FLAG)



- METHOD OF INSTALLATION:**
- CONTRACTOR TO DIG 6" MIN. TRENCH AND LINE TRENCH WITH FILTER FABRIC PRIOR TO BACKFILL.
 - EXCEPT FOR THE END POST, DRIVE ALL POSTS INTO THE GROUND AT BACK SIDE OF TRENCH SPACED A MAXIMUM OF 8 FT O.C.
 - ATTACH FILTER FABRIC TO POST AND STRETCH BETWEEN POSTS. SECURE FABRIC TO POST WITH METAL FASTENER AND REINFORCEMENT MATERIAL PLACED BETWEEN THE FASTENER AND THE GEOTEXTILE FABRIC.
 - POSTS SHALL BE CONSTRUCTED OF HARDWOOD WITH A MINIMUM DIAMETER THICKNESS OF 1-1/2 INCHES.

24" SILT FENCE

EASTCOAST
erosion blankets

443 Bicker Road
Berwyn, PA 19008
800-982-4005
610-488-8466 (ext.)
610-488-8404 (fax)
www.eastcoastblanks.com

Material and Performance Specification Sheet
ECC-2 Double Net Coconut Rolled Erosion Control Product

Description: The ECC-2 is made with uniformly distributed 100% coconut fiber and two polypropylene nets secured together with UV stabilized thread. The tightly compressed blankets are placed inside vertical bags and include a product label, side and installation guide. The blankets are patented for easy transportation.

The ECC-2 has functional longevity of approximately 36 months, but will vary depending on soil and climatic conditions and is suitable for slopes 1:1. The ECC-2 meets Type 4 specification requirements established by the Erosion Control Technology Council (ECTC) and Federal Highway Administration's (FHWA) PFD Section 173.1.1.

Material	Weight - Top and Bottom	Material	Weight
Heavyweight UV Stabilized Polypropylene	75"x20" Opening	100% Coconut Fiber	100 lbs/roll (50 yd)
UV Stabilized Thread		UV Stabilized	1.50" width spacing

Roll Size	Width	Length	Weight	Area	Standards	Weight	Area	
7.5' R.	7.5' R. (23.3 m)	96.0' R. (29.3 m)	46.0 yd (42.4 kg)	80 yd ² (66.9 m ²)	7.5' R. (23.3 m)	120.0' R. (36.6 m)	60.0 yd (55.2 kg)	100 yd ² (93.0 m ²)

Index Value Properties*

Property	Test Method	Typical
Moisture Content	ASTM D2013	1.5 %
Thickness	ASTM D1539	3/8" (9.5 mm)
Tensile Strength (MD)	ASTM D5035	200 LBS
Elongation (MD)	ASTM D5035	38 %
Tensile Strength (TD)	ASTM D5035	200 LBS
Elongation (TD)	ASTM D5035	38 %
Light Absorption	ECTC Calculation	24 %
Water Absorption	ASTM D1119	235 %

Penetration Test*

Property	Value
Penetration	4.5
Penetration	4.5
Maximum Permissible Shear Stress	3.3 psf (0.154 Pa)
Maximum Flow Velocity	7.0 ft/sec (2.13 m/sec)

Roach-Scale Testing* (ETPFP):


Test Method	Parameters	Results
ECTC Method 2	500mm (40") (16.4")	14.4
ECTC Method 2	1000mm (80") (25.4")	14.4
ECTC Method 2	1500mm (120") (30.5")	14.4
ECTC Method 2	2000mm (160") (40.6")	14.4
ECTC Method 2	2500mm (200") (51.8")	14.4
ECTC Method 2	3000mm (240") (63.0")	14.4
ECTC Method 2	3500mm (280") (76.2")	14.4
ECTC Method 2	4000mm (320") (89.3")	14.4
ECTC Method 2	4500mm (360") (106.7")	14.4
ECTC Method 2	5000mm (400") (127.0")	14.4
ECTC Method 2	5500mm (440") (152.4")	14.4
ECTC Method 2	6000mm (480") (177.8")	14.4
ECTC Method 2	6500mm (520") (203.2")	14.4
ECTC Method 2	7000mm (560") (228.6")	14.4
ECTC Method 2	7500mm (600") (254.0")	14.4
ECTC Method 2	8000mm (640") (274.3")	14.4
ECTC Method 2	8500mm (680") (304.8")	14.4
ECTC Method 2	9000mm (720") (335.3")	14.4
ECTC Method 2	9500mm (760") (365.8")	14.4
ECTC Method 2	10000mm (800") (396.3")	14.4

Proven Number of:


CCO
MNS
NAB

NOTE: CONTRACTOR TO INSTALL PER MANUFACTURER'S RECOMMENDATIONS.

EROSION CONTROL BLANKET DETAIL




HANDHELD SOIL PENETROMETER TEST




- NOTE:** SOIL COMPACTION TESTING LOCATIONS IDENTIFIED ARE RECOMMENDED LOCATIONS FOR GRADES/DISTURBED AREAS WITHIN THE VICINITY OF BUILDINGS AND STRUCTURES OR ON INDIVIDUAL LOTS. FOR GRADES/DISTURBED AREAS WITHIN OPEN OR COMMON SPACES, SOIL COMPACTION TESTING SHALL BE PERFORMED IN ACCORDANCE WITH THE FREQUENCY LISTED IN THE LEGEND (THIS SHEET).

TYPICAL SOIL COMPACTION TESTING LOCATIONS




NEW JERSEY SOIL EROSION AND SEDIMENT CONTROL DETAIL FOR CONSTRUCTION DEWATERING


STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY, SECTION 14, SEVENTH EDITION



TEMPORARY SOIL STOCKPILE



TREE PROTECTION



STAKED HAY BALE

Date	Description	No.
11/11/2022	NJDEP FHA SUBMISSION #4	5.
9/16/2022	NJDEP FHA SUBMISSION #3	4.
8/10/2022	NJDEP FHA SUBMISSION #2	3.
6/30/2022	DESIGN DEVELOPMENT FINAL	2.
6/9/2022	NJDEP FHA SUBMISSION	1.

REVISIONS

SIGNATURE CHRISTIAN ROCHE 8/8/2022
PROFESSIONAL ENGINEER NJ Lic. No. 24GE04988100

LANGAN
Langan Engineering and Environmental Services, Inc.
989 Lenox Drive, Suite 124
Lawrenceville, NJ 08648


T: 609.282.8000 F: 609.282.8001 www.langan.com
NJ CERTIFICATE OF AUTHORIZATION No. 24GE04988100

Project **CAMPUS OPERATIONS BUILDING - PRINCETON UNIVERSITY LAKE CAMPUS**
PRINCETON UNIVERSITY
WEST WINDSOR TOWNSHIP (BLOCK 3, LOT 1.012)


MERCER COUNTY NEW JERSEY
Drawing Title

SOIL EROSION AND SEDIMENT CONTROL DETAILS


Project No. 130183501	Drawing No. CE-502
Date 06/09/2022	
Drawn By CJS	
Checked By CMR	Sheet 9 of 14



REINFORCED CONCRETE PAD DETAIL




HDPE PIPE INSTALLATION DETAIL (STORM)




DOMESTIC AND FIRE WATER MAINS AND SERVICES TO BE INSTALLED WITH MINIMUM OF 4" OF COVER.

NON-SANITARY SEWER - SITE TRENCH AND BEDDING




- NOTES:**
1. FRAME AND GRATE TO BE CAMPBELL FOUNDRY NO. 3425 (TYPE 'E') SOLID COVER OR APPROVED EQUAL.
 2. FOOTER AND INVERT TO BE NJDOT CLASS "C" CONCRETE.
 3. PROVIDE STEPS 12" O.C.
 4. CONCRETE STRUCTURE TO BE DESIGNED TO AASHTO HS-20 LOADING.
 5. CONCRETE TO TEST TO 4,500 PSI @ 28 DAYS.
 6. CONCRETE STRUCTURE REINFORCING AS PER ASTM A-185.
 7. BRING FRAME AND GRATE TO GRADE WITH BRICK AND MORTAR.
 8. FIRST STEP NOT TO EXCEED 12 INCHES FROM TOP OF GRATE.
 9. PROVIDE SHOP DRAWINGS FOR REVIEW.
 10. DETAIL INDICATES MINIMUM STRUCTURE DIMENSIONS. LARGER DIMENSIONS MAY BE REQUIRED FOR LARGER PIPES.


UNDERGROUND BASIN OUTLET STRUCTURE (OCS-1)




- GENERAL NOTES:**
1. ALL ANCHOR BOLTS, NUTS AND WASHERS TO BE GALVANIZED.
 2. FRAME AND GRATE TO BE CAMPBELL FOUNDRY NO. 3425 OR FABRICATED ALUMINUM GRATE.
 3. ORIFICE TRASH RACK FRAME TO BE HINGED.
 4. PROVIDE SHOP DRAWINGS FOR STRUCTURES AND APPURTENANCES.




INFILTRATION BASIN OUTLET STRUCTURE (OCS-2)




TYPE 'B' INLET




SANITARY SEWER TRENCH




PRECAST CONCRETE SANITARY MANHOLE




WEST WINDSOR TOWNSHIP SANITARY MANHOLE COVER




PRINCETON UNIVERSITY SANITARY MANHOLE COVER



ELECTRIC CONDUIT DUCT BANK



REINFORCED TURF



WEST WINDSOR TOWNSHIP SANITARY CLEANOUT

Date	Description	No.
11/11/2022	NJDEP FHA SUBMISSION #4	5.
9/16/2022	NJDEP FHA SUBMISSION #3	4.
8/10/2022	NJDEP FHA SUBMISSION #2	3.
6/30/2022	DESIGN DEVELOPMENT FINAL	2.
6/9/2022	NJDEP FHA SUBMISSION	1.

REVISIONS



SIGNATURE: CHRISTIAN ROCHE
PROFESSIONAL ENGINEER NJ Lic. No. 24GE04988100

LANGAN
Langan Engineering and Environmental Services, Inc.
989 Lenox Drive, Suite 124
Lawrenceville, NJ 08648
T: 609.282.8000 F: 609.282.8001 www.langan.com
NJ CERTIFICATE OF AUTHORIZATION No. 24GA27986400



Project: **CAMPUS OPERATIONS BUILDING - PRINCETON UNIVERSITY LAKE CAMPUS**
PRINCETON UNIVERSITY
WEST WINDSOR TOWNSHIP (BLOCK 3, LOT 1.012)
MERCER COUNTY NEW JERSEY
Drawing Title

CONSTRUCTION DETAILS

Project No.	Drawing No.
130183501	CS-501
Date	06/09/2022
Drawn By	CJS
Checked By	CMR
	Sheet 12 of 14



<p>444-LA File Name: 020-444LA Issue Date: 2018 PO Box 323, Wilsonville, Oregon 97070-0323 Tel: (503) 662-2844 Fax: (503) 662-2807</p>	<p>444-LA File Name: 020-444LA Issue Date: 2018 PO Box 323, Wilsonville, Oregon 97070-0323 Tel: (503) 662-2844 Fax: (503) 662-2807</p>	<p>444-LA File Name: 020-444LA Issue Date: 2018 PO Box 323, Wilsonville, Oregon 97070-0323 Tel: (503) 662-2844 Fax: (503) 662-2807</p>	<p>444-LA File Name: 020-444LA Issue Date: 2018 PO Box 323, Wilsonville, Oregon 97070-0323 Tel: (503) 662-2844 Fax: (503) 662-2807</p>
--	--	--	--




PIPE SIZE	THRUST BLOCK SCHEDULE															
	TEE	22 1/2	45	90	W											
	L	D	L	D	L	D	L	D	L	D	L	D	L	D		
6"	18"	15"	15"	12"	15"	12"	15"	15"	21"							
8"	2'	18"	18"	12"	18"	12"	2'	18"	2'							
12"	3'	2'	2'	12"	2'	12"	3'	2'	28"							
16"	4'	2.5'	2'	12"	2.33'	15"	4'	2.5'	31"							
20"	5.25'	3'	2'	18"	3'	2'	5.25'	3'	33"							
24"	7.5'	3'	3'	18"	4'	2.5'	7.5'	3'	3'							

BASIS:
2,000 LB/SQ.FT. SOIL RESISTANCE 250
PSI WATER PRESSURE CORRECTION
FACTORS FOR OTHER SOILS:
SOFT CLAY 4
SAND 2
SAND & GRAVEL 1.33
SHALE 0.4


NOTE:
1. IF SOFT MATERIALS ARE ENCOUNTERED, THE
THRUST BLOCKS SIZES SHALL BE ADJUSTED
ACCORDINGLY.
2. CONCRETE TO BE 3000 PSI.

ELECTRIC MANHOLE DETAIL




- NOTES:
1. BASIN SECTION TO MEET NEW JERSEY BEST MANAGEMENT PRACTICE MANUAL STANDARDS.
 2. THE BASIN FOOTPRINT SHALL BE PROTECTED THROUGH CONSTRUCTION AND REMAIN FREE OF CONSTRUCTION TRAFFIC TO PREVENT SOIL COMPACTION.
 3. THE AREA OF THE SITE DRAINING TO THE PROPOSED BASIN MUST BE COMPLETELY STABILIZED PRIOR TO USE OF THE PROPOSED INFILTRATION BASIN.
 4. BASIN INLET PIPES SHALL DISCHARGE TO THE PROPOSED SCOUR HOLE THAT SHALL BE CONSTRUCTED WITH A MINIMUM VOLUME OF 235CF TO PROVIDE 10% STORAGE TO THE WATER QUALITY DESIGN STORM EVENT WHICH DRAINS TO THE PROPOSED INFILTRATION BASIN (SEE SCOUR HOLE DETAIL).
 5. BASIN SIDE SLOPES SHALL NOT EXCEED 3:1.
 6. SAND LAYER:
 - 6.1. TO BE INSTALLED AT A MINIMUM DEPTH OF 6"
 - 6.2. SAND MUST MEET ALL SPECIFICATIONS FOR CLEAN, MEDIUM-AGGREGATE CONCRETE SAND IN ACCORDANCE WITH AASHTO M-6 OR ASTM C-33, AS CERTIFIED BY A LICENSED NJPE.
 - 6.3. THE MAXIMUM PERCENTAGE OF FINES IS 15%.
 - 6.4. THE MINIMUM TESTED PERMEABILITY SHALL BE 20 INCHES/HOUR.

2-WAY CLEANOUT DETAIL




- NOTES:
1. SIZE AND BEARING FOR THRUST BLOCK SHALL CONFORM TO CURRENT A.W.W.A. STANDARDS, OR SHALL BE DESIGNATED ON THE PLANS.
 2. CONCRETE FOR THE THRUST BLOCKS TO BE N.J.D.O.T., CLASS "C".
 3. ALL CONNECTIONS TO BE MECHANICAL JOINT, OR LOCK RING TYPE JOINTS, AS SPECIFIED.
 4. GATE VALVES SHALL BE USED ON MAINS LESS THAN 16" IN DIAMETER.



GATE VALVE ASSEMBLY



GRAVEL ACCESS ROAD



THRUST BLOCKS



ANTI-SEEP COLLAR

- NOTES:
1. MEASURES SHOULD BE TAKEN TO PREVENT MIGRATION OF NATIVE FINES INTO BACKFILL MATERIAL WHEN REQUIRED.
 2. ALL INSTALLATION AND MATERIALS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
 3. REFER TO SOILING AND DRAINAGE PLAN FOR TOTAL NUMBER OF PIPES AND LAYOUT.
 4. BASIN SECTION TO MEET NEW JERSEY BEST MANAGEMENT PRACTICE MANUAL STANDARDS.
 5. THE BASIN FOOTPRINT SHALL BE PROTECTED THROUGH CONSTRUCTION AND REMAIN FREE OF CONSTRUCTION TRAFFIC TO PREVENT SOIL COMPACTION.
 6. BASIN SHALL RECEIVE FLOW FROM ROOF OF PROPOSED BUILDING AND VERTICAL COVERAGE TO BE DISCHARGED INTO BASIN. PROPOSED BUILDING GUTTER SYSTEM TO BE INSTALLED TO GUTTER SCREENS.

SUBSURFACE INFILTRATION BASIN



BIKE BOLLARD



INFILTRATION BASIN DETAIL

Date	Description	No.
11/11/2022	NJDEP FHA SUBMISSION #4	5.
9/16/2022	NJDEP FHA SUBMISSION #3	4.
8/10/2022	NJDEP FHA SUBMISSION #2	3.
6/30/2022	DESIGN DEVELOPMENT FINAL	2.
6/9/2022	NJDEP FHA SUBMISSION	1.

REVISIONS

SIGNATURE CHRISTIAN ROCHE 8/10/2022
PROFESSIONAL ENGINEER NJ Lic. No. 24GE04988100

LANGAN
Langan Engineering and Environmental Services, Inc.
989 Lenox Drive, Suite 124
Lawrenceville, NJ 08648

T: 609.282.8000 F: 609.282.8001 www.langan.com
NJ CERTIFICATE OF AUTHORIZATION No. 24GE04988100

Project
CAMPUS OPERATIONS BUILDING - PRINCETON UNIVERSITY LAKE CAMPUS
PRINCETON UNIVERSITY
WEST WINDSOR TOWNSHIP (BLOCK 3, LOT 1.012)

MERCER COUNTY NEW JERSEY
Drawing Title

CONSTRUCTION DETAILS

Project No.	130183501	Drawing No.	CS-502
Date	06/09/2022	Sheet 13 of 14	
Drawn By	CJS		
Checked By	CMR		

SURVEY NOTES:

1. SITE FEATURES AND TOPOGRAPHIC INFORMATION WITHIN THE SURVEY PROJECT LIMIT LINE IS THE RESULT OF A FIELD SURVEY PERFORMED BY VAN NOTE-HARVEY ASSOCIATES INC, NOVEMBER 2019.
2. SITE FEATURES OUTSIDE OF THE SURVEY PROJECT LIMIT LINE HAVE BEEN COMPILED FROM RECORD INFORMATION AND HAVE NOT BEEN FIELD VERIFIED FOR EXISTENCE AND/OR ACCURACY. THIS INFORMATION IS PORTRAYED FOR PICTORIAL PURPOSES ONLY AND CANNOT BE RELIED UPON AS ACCURATE.
3. THE HORIZONTAL DATUM FOR THIS SURVEY IS A MODIFIED GROUND SYSTEM, ESTABLISHED AS VNHA-PU 2017 SURVEY CONTROL NETWORK, BASED ON THE NEW JERSEY STATE PLANE COORDINATE SYSTEM (NJSPCS) NORTH AMERICAN DATUM (NAD 1983), NATIONAL ADJUSTMENT (NA) 2011.
4. THE VERTICAL DATUM FOR THIS SURVEY IS THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88).

DEMOLITION NOTES:

1. IF HAZARDOUS MATERIALS ARE ENCOUNTERED DURING DEMOLITION OR REMOVAL OPERATIONS, THE CONTRACTOR SHALL IMMEDIATELY STOP WORK AND REPORT SUCH FINDINGS TO THE OWNER.
2. CONTRACTOR SHALL PROTECT EXISTING UTILITIES TO REMAIN DURING SAWCUTTING, DEMOLITION AND SITE CONSTRUCTION.
3. CONTRACTOR SHALL LOCATE EXISTING GAS LINES PRIOR TO ANY WORK. THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING NJ ONE CALL PRIOR TO ANY EXCAVATION ON SITE.
4. EXISTING UTILITY SERVICES WITHIN DEMOLITION AREA SHALL BE VERIFIED BY THE CONTRACTOR IN THE FIELD. WHEN NOTED, UTILITY SERVICES SHALL BE DISCONNECTED & CUT & CAPPED AT THE PROJECT BOUNDARY.
5. THE CONTRACTOR SHALL MAKE PROVISIONS TO ADDRESS UTILITIES AND DRAINAGE DURING CONSTRUCTION SUCH THAT POSITIVE DRAINAGE IS ALWAYS PROVIDED AND MAINTAINED UTILITY SERVICES REMAIN UNINTERRUPTED.
6. THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON VARIOUS RECORDS AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING COMPLETE OR EXACT. THE CONTRACTOR MUST NOTIFY ALL APPROPRIATE UTILITY COMPANIES BEFORE ANY DEMOLITION OR EXCAVATION. CONTRACTOR IS RESPONSIBLE FOR CONTACTING NJ ONE CALL PRIOR TO ANY EXCAVATION.
7. ALL DEMOLITION WORK TO BE IN ACCORDANCE WITH LOCAL, STATE, AND FEDERAL REGULATIONS.
8. ITEMS TO BE SALVAGED SHALL BE COORDINATED WITH PRINCETON UNIVERSITY. THESE ITEMS INCLUDE, BUT ARE NOT LIMITED TO, CATCH BASIN AND MANHOLES FRAMES, GRATES AND RIMS, BLUE-STONE, SIGNS, LIGHT POLES, AND RETAINING WALL STONES. ALL REFUSE AS A RESULT OF DEMOLITION SHALL BE DISPOSED OF IN ACCORDANCE WITH ALL APPLICABLE CODES AND ORDINANCES.
9. THE CONTRACTOR SHALL INSPECT THE SITE THOROUGHLY AND FIELD-VERIFY THE LOCATION AND DEPTH OF ALL EXISTING UTILITIES. CONTRACTORS USING THESE PLANS FOR DEMOLITION OR CONSTRUCTION SHALL CONFIRM ALL UTILITIES IN THE FIELD TO ESTABLISH LOCATIONS, SIZES, MATERIALS, AND ELEVATIONS. ANY DISCREPANCIES SHALL IMMEDIATELY BE BROUGHT TO THE ATTENTION OF THE OWNER AND THE ENGINEER.
10. THE CONTRACTOR SHALL INCLUDE IN THEIR BID ALL TEMPORARY FACILITIES AND SERVICES NECESSARY TO SATISFY FEDERAL, STATE, AND LOCAL REQUIREMENTS INCLUDING BUT NOT NECESSARILY LIMITED TO BRACING, SHORING, PAVEMENT REPAIR, FENCING, PEDESTRIAN AND VEHICLE ACCESS, ETC.
11. CONTRACTOR TO INSTALL APPROVED SOIL EROSION AND SEDIMENT CONTROL MEASURES PRIOR TO THE START OF WORK. CONTRACTOR MUST NOTIFY MCSCD USING THEIR 48-HOUR START OF LAND DISTURBANCE NOTIFICATION FORM.
12. CONTRACTOR TO NOTIFY THE TOWNSHIP ENGINEER AT LEAST 48 HOURS PRIOR TO THE START OF DEMOLITION.
13. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY DEMOLITION-ASSOCIATED PERMITS.
14. THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONARY AND PROTECTIVE MEASURES, INCLUDING BUT NOT LIMITED TO SIGNS, LIGHTS, FENCES, BARRIERS, AND PEDESTRIAN AND TRAFFIC CONTROL MEASURES.
15. ALL UTILITY SERVICES TO BE REMOVED/RELOCATED BY THE CONTRACTOR SHALL BE TERMINATED AND CERTIFIED PRIOR TO THE START OF THE DEMOLITION WORK. CONTRACTOR IS TO CONTACT THE APPROPRIATE UTILITY COMPANIES FOR ALL WORK WITH EXISTING UTILITIES. REMOVAL OF WATER AND SEWER ARE TO BE PERFORMED IN ACCORDANCE WITH TOWNSHIP AND UTILITY PURVEYOR STANDARDS. COORDINATE ALL WORK WITH UTILITY PURVEYOR AND PRINCETON UNIVERSITY
16. EXISTING UTILITIES SHALL BE REMOVED WITHIN THE PROJECT LIMITS, NOT ABANDONED IN PLACE. EXISTING UTILITIES SHALL BE CUT/CAPPED AT THE PROJECT LIMIT AND ABANDONED IN PLACE OUTSIDE OF THE PROJECT LIMITS. EXISTING UTILITIES SHALL BE PLUGGED OR RECEIVE A CONCRETE BULKHEAD.
17. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY IF ANY UNEXPECTED UNDERGROUND UTILITY SYSTEMS, INCLUDING UNDERGROUND STORAGE TANKS, ARE ENCOUNTERED.
18. THE CONTRACTOR SHALL REMOVE AND PROPERLY BACKFILL UNDERGROUND UTILITIES AND STORM DRAINS AS INDICATED ON THE PLANS. THE CONTRACTOR SHALL VERIFY THE UPSTREAM SOURCE, IF APPLICABLE, FOR ALL UTILITIES TO BE REMOVED OR RELOCATED. THE CONTRACTOR SHALL MAINTAIN ANY UPSTREAM EXISTING UTILITIES TO REMAIN UNTIL THE RELOCATED SERVICE HAS BEEN INSTALLED.
19. SOIL MATERIAL AND DEMOLITION DEBRIS REMOVAL WILL BE REQUIRED. DISPOSAL SHALL BE IN ACCORDANCE WITH LOCAL, STATE, AND FEDERAL REGULATIONS. ANY CONSTRUCTION MATERIAL OR SOIL THAT LEAVES THE SITE FOR DISPOSAL AND/OR RECYCLING MUST BE SENT TO A FACILITY THAT IS PRE-APPROVED BY PRINCETON FACILITIES OPERATIONS CIVIL & ENVIRONMENTAL ENGINEERING DEPARTMENT. THIS INCLUDES BUT IS NOT LIMITED TO DEMOLITION WASTE, CONCRETE, ASPHALT AND SOIL. IN SOME CASES THE MATERIAL WILL NEED TO BE TESTED PRIOR TO LEAVING UNIVERSITY PROPERTY WITH PRINCETON APPROVED SAMPLING PROTOCOL AND RESULTS.
20. DURING DEMOLITION AND DEBRIS REMOVAL OPERATIONS, CONTRACTOR SHALL CONTINUALLY USE WATER SPRINKLING AND OTHER SUITABLE METHODS TO MINIMIZE THE AMOUNT OF DUST AND DIRT, RISING AND SCATTERING IN THE AIR, TO THE LOWEST PRACTICAL LEVEL POSSIBLE.
21. TREES TO BE REMOVED SHALL HAVE STUMPS GROUND AND REMOVED IN THEIR ENTIRETY. ROOTS SHALL ALSO BE FULLY REMOVED. STUMP AND ROOT DEBRIS SHALL BE REMOVED FOR THE SITE AND THE HOLE SHALL BE BACKFILLED WITH APPROVED COMPACTED FILL.
22. CONTRACTOR TO VERIFY EXTENTS OF UTILITY DEMOLITION WITH UTILITY OWNERS. IF NEEDED, CONTRACTOR SHALL PROVIDE TEMPORARY UTILITY LINES TO IMPACTED BUILDINGS DURING UTILITY INSTALLATION/DEMOLITION WORK. UTILITY SERVICE TO EXISTING BUILDINGS TO REMAIN SHALL NOT BE DISRUPTED.
23. FOR ASPHALT DEMOLITION WITHIN CRITICAL ROOT ZONE OF EXISTING TREES TO REMAIN: CONTRACTOR SHALL SCRAPE OFF ASPHALT LAYER, EXPOSING STONE BASE. REMOVE STONE BASE BY HAND, TAKING CARE NOT TO DAMAGE TREE ROOTS. COVER TREE ROOTS TO MATCH FINAL GRADES AND STABILIZE.
24. FOR CONCRETE DEMOLITION WITHIN CRITICAL ROOT ZONE OF EXISTING TREES TO REMAIN: CONTRACTOR SHALL JACKHAMMER CONCRETE AND LIFT STRAIGHT UP, EXPOSING STONE BASE. REMOVE STONE BASE BY HAND, TAKING CARE NOT TO DAMAGE TREE ROOTS. COVER ROOTS WITH SOIL TO MATCH FINAL GRADES AND STABILIZE.

GRADING AND DRAINAGE NOTES:

1. ALL EXISTING FRAMES, COVERS, AND GRATES IN AREAS WHERE GRADES WILL BE REVISED BY FILLING OR CUTTING, OR PAVEMENT OVERLAY, MUST BE RESET TO MATCH FINAL GRADE (THIS INCLUDES MANHOLES, HANDHOLES, VALVE BOXES, INLETS, ETC.) IN AREAS OF CUT, CONTRACTOR SHALL PROVIDE REQUIRED COVERAGE OF UTILITY AND STORMWATER LINES AS SPECIFIED BY THE UTILITY PURVEYOR.
2. CONTRACTOR IS RESPONSIBLE FOR LOCATING UTILITY CROSSINGS AND PROVIDING UTILITY DROPS AS REQUIRED. CONTRACTOR SHALL NOTIFY ENGINEER IMMEDIATELY IF CROSSING CONFLICT OCCURS.
3. TEST PITS WILL BE REQUIRED TO CONFIRM ADEQUATE CLEAR DISTANCES BETWEEN PROPOSED AND EXISTING UTILITIES. TEST PITS SHALL BE PERFORMED BY THE CONTRACTOR PRIOR TO THE START OF CONSTRUCTION.
4. ALL GRADING, DRAINAGE, AND UTILITY INSTALLATION AND/OR CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH LOCAL REQUIREMENTS.
5. GRADE ALL AREAS OTHER THAN PAVED GRADED AREAS AND BUILDINGS, INCLUDING EXCAVATED AREAS, FILLED AND TRANSITION AREAS, AND LANDSCAPED AREAS TO FINISH GRADE ELEVATIONS OR CONTOURS AS INDICATED ON DRAWINGS. FINISHED SUBGRADE SURFACE SHALL BE UNIFORM AND SMOOTH, FREE FROM ROCK, DEBRIS, OR IRREGULAR SURFACE CHANGES. SITE SHALL BE GRADED TO ALLOW FOR PROPER DRAINAGE WITHOUT PONDING AND IN A MANNER THAT WILL MINIMIZE EROSION POTENTIAL.
6. SITE GRADING SHALL NOT PROCEED UNTIL ALL EROSION CONTROL MEASURES HAVE BEEN INSTALLED.
7. CONTRACTOR IS RESPONSIBLE FOR PREVENTING SOIL AND SEDIMENT-LADEN RUNOFF FROM STORMWATER AND DEWATERING ACTIVITIES FROM ENTERING EXISTING OR PROPOSED STORMWATER FACILITIES.

SOILS NOTES:

1. PER NRCS SOIL MAPPING, SITE SOILS INCLUDE BIRDSBORO GRAVELLY SOLUM VARIANT SOILS (BHSGB), BOWMANVILLE SILT LOAM (BoyAt), UDORTHERTS (Udgb) AND MARSH (MbOAt).
2. REFER TO SHEET CE-501 AND CE-502 FOR SOIL EROSION AND SEDIMENT CONTROL NOTES AND DETAILS.
3. RESTORE AND MAINTAIN THE STABILIZED CONSTRUCTION ENTRANCE AT ALL ACCESS POINTS.
4. ALL SOIL WASHED, DROPPED, SPILLED OR TRACKED OUTSIDE THE LIMITS OF DISTURBANCE SHOWN HEREON WILL BE REMOVED IMMEDIATELY TO PREVENT WASHING OR TRACKING OF SOIL AWAY FROM THE PROJECT AREA AND AS A MINIMUM, PRIOR TO THE COMPLETION OF CONSTRUCTION EACH DAY.
5. DUST SHALL BE CONTROLLED DURING CONSTRUCTION VIA THE APPLICATION OF WATER UNTIL THE SURFACE IS WET, OR OTHER APPROVED METHOD IN ACCORDANCE WITH SECTION 16-1 OF THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY.
6. ANY TEMPORARY RIDING SURFACE WITHIN ROADWAYS MUST BE 3/4" CLEAN STONE, DGA, CRUSHED CONCRETE, COLD PATCH OR BASE PAVEMENT. TEMPORARY RIDING SURFACES CONSISTING OF SOIL WILL NOT BE PERMITTED.
7. TEMPORARY TOPSOIL STOCKPILES, CONTRACTOR PARKING & CONSTRUCTION STAGING AREAS SHALL BE LOCATED IN THE APPROVED LIMIT OF DISTURBANCE.
8. ANY DAMAGED CURB, SIDEWALKS AND HARDSCAPE SHALL BE REPAIRED/RECONSTRUCTED AS REQUIRED.
9. EXISTING UTILITIES SHOWN TO REMAIN ON THE SITE DEMOLITION PLAN ARE TO BE PROTECTED DURING ALL CONSTRUCTION ACTIVITIES.
10. GRADING WITHIN TREE PROTECTION AREAS SHALL BE PERFORMED WITHOUT THE USE OF HEAVY MACHINERY/EQUIPMENT.
11. CONTRACTOR TO PROVIDE SILT FENCE AND CONSTRUCTION ENTRANCE AS NECESSARY TO PREVENT SEDIMENT FROM ENTERING THE SURROUNDING STORM SYSTEM.
12. CONTRACTOR TO INSTALL A TEMPORARY CHAIN LINK FENCE AS NECESSARY TO PROVIDE A SAFE WORK SITE. CONTRACTOR IS RESPONSIBLE FOR SAFE PEDESTRIAN ACCESS THROUGHOUT CONSTRUCTION. CONTRACTOR TO RELOCATE TEMPORARY CONSTRUCTION FENCE AS NECESSARY TO ACCOMMODATE WORK THROUGHOUT THE PROJECT.

CONTRACTOR SHALL SUBMIT SHOP DRAWINGS FOR ALL DETAILS TO THE OWNER'S ENGINEER FOR REVIEW

CONTRACTOR SUBMITTAL NOTE

GENERAL CONSTRUCTION NOTES:

1. THESE PLANS REPRESENT OVERALL SITEWORK IMPROVEMENTS REQUIRED FOR DEMOLITION AND ENABLING WORK FOR THE CAMPUS OPERATIONS BUILDING - PRINCETON NURSERIES PROJECT. THE WORK TO BE PERFORMED IS SHOWN ON THE DRAWINGS. THE CONTRACTOR IS RESPONSIBLE FOR MEANS AND METHODS OF CONSTRUCTION; AS SUCH, THESE PLANS DO NOT COMPLETELY REPRESENT ALL SPECIFIC SITE DETAILS OF INSTALLATION REQUIRED FOR SITEWORK CONSTRUCTION. CONTRACTOR IS RESPONSIBLE TO PROVIDE ALL IMPROVEMENTS REQUIRED TO ACHIEVE CONSTRUCTION DEPICTED ON THESE PLANS.
 2. THE CONTRACTOR SHALL PROVIDE WRITTEN REQUESTS FOR INFORMATION TO THE OWNER AND OWNER'S ENGINEER PRIOR TO THE CONSTRUCTION OF ANY SPECIFIC SITEWORK ITEM IF ANY SITEWORK ITEM DEPICTED ON THE PLANS WARRANTS ADDITIONAL ENGINEERING INFORMATION REQUIRED FOR CONSTRUCTION AND IS NOT RELATED TO MEANS AND METHODS OF CONSTRUCTION. THE CONTRACTOR SHALL BE SPECIFICALLY RESPONSIBLE FOR SITEWORK ITEMS INSTALLED DIFFERENTLY THAN INTENDED AS DEPICTED ON THE PLANS IN THE ABSENCE OF SUBMITTING AND RECEIVING REVIEWS AND/OR DIRECTION ON WRITTEN REQUESTS FOR INFORMATION.
 3. THE CONTRACTOR SHALL ACCEPT THE SITE AS IS. THE CONTRACTOR SHALL MAKE A THOROUGH SITE INSPECTION IN ORDER TO FIELD CHECK EXISTING SITE CONDITIONS, CORRELATE CONDITIONS WITH THE DRAWINGS AND RESOLVE ANY POSSIBLE CONSTRUCTION CONFLICTS WITH THE OWNER AND OWNER'S ENGINEER PRIOR TO COMMENCEMENT OF WORK. THIS INCLUDES A TOPOGRAPHIC SURVEY OF ALL AREAS THE CONTRACTOR REQUIRES ADDITIONAL TOPOGRAPHIC INFORMATION. ANY CONDITIONS THAT DIFFER FROM THE SURVEY SHOWN ON THE DRAWINGS THAT ARE NOT BROUGHT TO THE ATTENTION OF THE OWNER AND OWNER'S ENGINEER PRIOR TO THE START OF WORK SHALL NOT BE CONSIDERED GROUNDS FOR A CHANGE ORDER.
 4. INFORMATION RELATED TO ELEVATIONS AND PROPOSED UTILITIES (SUCH AS ROADWAY GRADES, INVERT ELEVATIONS, RIM ELEVATIONS, GRATE ELEVATIONS, BUILDING FINISHED FLOOR ELEVATIONS, ETC.) MAY BE FOUND IN MORE THAN ONE LOCATION ON THE DRAWINGS. CONTRACTOR SHALL SPECIFICALLY REVIEW ALL PLANS, PROFILES AND ANY INFORMATION/DATA TABLES FOR CONSISTENCY PRIOR TO CONSTRUCTION. ANY INCONSISTENCIES OR DISCREPANCIES THAT ARE FOUND SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE OWNER'S ENGINEER IN WRITING PRIOR TO CONSTRUCTION.
 5. THERE ARE ADDITIONAL NOTES, SPECIFICATIONS AND REQUIREMENTS CONTAINED ON SHEETS THROUGHOUT THE PLAN SET AND AVAILABLE REFERENCES TO SPECIFICATIONS FROM APPLICABLE GOVERNING AUTHORITIES AND INDUSTRY STANDARDS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN, REVIEW AND ADHERE TO ALL APPLICABLE REQUIREMENTS.
- UTILITY NOTES:**
1. THE TOWNSHIP ENGINEER SHALL BE NOTIFIED IN ADVANCE OF SEWER INSTALLATION. NO SEWERS SHALL BE INSTALLED WITHOUT INSPECTION BY THE TOWNSHIP ENGINEER.
 2. THE CONTRACTOR SHALL PERFORM AN INFILTRATION OR A LOW PRESSURE EXFILTRATION TEST, DEFLECTION TEST, AIR TEST AND VIDEO INSPECTION (VIA CLOSED-CIRCUIT TELEVISION) ON EACH SECTION OF SEWER PIPE BETWEEN MANHOLES. THE TOWNSHIP ENGINEER SHALL DESIGNATE THE TYPE OF TEST TO BE PERFORMED AND THE MANNER IN WHICH IT SHALL BE CONDUCTED. THE TEST SHALL BE WITNESSED BY THE TOWNSHIP ENGINEER.
 3. ALL SEWER WORK SHALL BE DONE IN ACCORDANCE WITH THE TOWNSHIP RULES AND REGULATIONS AND STANDARD DETAILS.
 4. ALL PROPOSED UTILITIES SHALL BE INSTALLED UNDERGROUND AND COORDINATED WITH APPLICABLE UTILITY COMPANIES.
 5. EXISTING UTILITY INFORMATION SHOWN HEREON HAS BEEN COLLECTED FROM VARIOUS SOURCES AND IS NOT GUARANTEED AS TO ACCURACY OR COMPLETENESS. THE CONTRACTOR SHALL VERIFY ALL INFORMATION TO HIS/HER SATISFACTION PRIOR TO EXCAVATION. WHERE EXISTING UTILITIES ARE TO BE CROSSED BY PROPOSED CONSTRUCTION, TEST PITS SHALL BE DUG BY THE CONTRACTOR PRIOR TO CONSTRUCTION TO ASCERTAIN EXISTING INVERTS, MATERIALS, AND SIZES. TEST PIT INFORMATION SHALL BE GIVEN TO THE ENGINEER PRIOR TO CONSTRUCTION TO PERMIT ADJUSTMENTS AS REQUIRED TO AVOID CONFLICTS.
 6. THE CONTRACTOR SHALL CALL THE "ONE NUMBER TO CALL SYSTEM" 1-800-272-1000, NOT LESS THAN 72 HOURS NOR MORE THAN 10 WORKING DAYS PRIOR TO PLANNED WORK TO NOTIFY UTILITY OWNERS OF THE INTENT TO START WORK. THE CONTRACTOR IS RESPONSIBLE FOR NOTIFYING "PRIVATE" NON-MEMBER UTILITY OWNERS INDIVIDUALLY. ALL WORK SHALL BE COORDINATED WITH UTILITY OWNERS INCLUDING, BUT NOT LIMITED TO, PUBLIC SERVICE ELECTRIC AND GAS CO., VERIZON TELEPHONE CO., THE SERVICING WATER COMPANY, PRIOR TO THE START OF CONSTRUCTION (IF REQUIRED).
 7. FINAL BUILDING ENTRY LOCATIONS OF ALL UTILITY PER FINAL MEP PLANS.

11/11/2022	NJDEP FHA SUBMISSION #4	5.
9/16/2022	NJDEP FHA SUBMISSION #3	4.
8/10/2022	NJDEP FHA SUBMISSION #2	3.
6/30/2022	DESIGN DEVELOPMENT FINAL	2.
6/9/2022	NJDEP FHA SUBMISSION	1.
Date	Description	No.

REVISIONS

SIGNATURE CHRISTIAN ROCHE 8/10/2022
PROFESSIONAL ENGINEER NJ Lic. No. 24GE04988100



Langan Engineering and Environmental Services, Inc.
989 Lenox Drive, Suite 124
Lawrenceville, NJ 08648

T: 609.282.8000 F: 609.282.8001 www.langan.com
NJ CERTIFICATE OF AUTHORIZATION No. 24GA27896400

Project
CAMPUS OPERATIONS BUILDING - PRINCETON UNIVERSITY LAKE CAMPUS
PRINCETON UNIVERSITY
WEST WINDSOR TOWNSHIP (BLOCK 3, LOT 1.012)

MERCER COUNTY NEW JERSEY
Drawing Title

CONSTRUCTION DETAILS

Project No. 130183501	Drawing No. CS-503
Date 06/09/2022	
Drawn By CJS	
Checked By CMR	
Sheet 14 of 14	